

**CONTRACT DOCUMENTS
BOONE COUNTY, MISSOURI
Addition to the Juvenile Justice Center
BID NO: 59-16SEP03**

ADDENDUM #2

This addendum is issued in accordance with the Instructions to Bidders and is hereby incorporated into and made a part of the Contract Documents. Bidders are reminded that receipt of this addendum should be acknowledged and submitted with bidder's *Response Form*.


Specifications for the above noted Request for Bid and the work covered thereby are herein modified as follows, and except as set forth herein, otherwise remain unchanged and in full force and effect:

BID DOCUMENTS:

ADD to bid the attached clarifications and/or modifications to be made in the plans and project manual for the above referenced bid.

PLEASE NOTE: This does not change the bid opening date. Bids are due at the Boone County Purchasing Office, Johnson Building, 601 E. Walnut, Room 208, Columbia, Missouri, 65201-7731, no later than 9:15 a.m., Tuesday, September 23, 2003.

The bid is scheduled to be opened after 9:30 a.m., Tuesday, September 23, 2003 by the Boone County Commission, Commission Chambers, 801 E. Walnut, Columbia, Missouri 65201.

By: 
Marlene Ridgway
Buyer

BIDDER has examined copy of Addendum #2 to Bid Number 59-16SEP03 – Addition to the Juvenile Justice Center, receipt of which is hereby acknowledged:

Company Name: _____

Address: _____

Phone Number: _____

Fax Number: _____

Authorized Representative Signature: _____

Date: _____

September 19, 2003

ADDENDUM NO. TWO

Addition and Renovations to
Juvenile Justice Center
5665 Roger I. Wilson Memorial Dr.
Columbia, MO 65202
Bid Number 59-16SEP03

Bidders are hereby informed of the following clarifications and/or modifications to be made in the plans and project manual for the above referenced project.

1. Project Manual, Section 9.14 – FRP (Fiberglass Reinforced Polyester) Panels.
Clarification: "Male Day Room No. 36A, Detention Rooms B09 thru B20 and Rooms No. 36B thru No. 36J - Install FRP panels directly to 5/8" gypsum board ceilings as shown by Wall Sections M/A4, A/A5 and B/A5. Delete references to lay-in ceiling panels as per Items 9.14.B.3. thru 9.14.B.5."
2. Project Manual, 15930: Duct Insulation – The intent of the specs is the following:
Clarifications:
 - a. All rectangular ductwork shall be internally insulated with ½", 2 lb./c.f. ductwork insulation.
 - b. All round ductwork shall be externally insulated with 1" thick glass fiber insulation with vapor barrier."
3. Drawings Sheets S201, Foundation Plan 1/S201.
Clarification: "Move Grid X.1 and new pre-engineered frame 8" to the west."
4. Drawings Sheet A2, Floor Plan A/A2.
Clarification: "Classroom 49A – Install random VCT color accent tiles to match existing pattern in Classroom No. 49."
5. Drawings Sheet A4, Soffit Detail M/A4.
Clarification: "Extend face of new soffit 3'-6" to the west."