

**CONTRACT DOCUMENTS
BOONE COUNTY, MISSOURI
BID #54-20JUN06 Boothe Lane Culvert Replacement Project**

**ADDENDUM #1
(Issued June 14, 2006)**


This addendum is issued in accordance with the Introduction and General Conditions of Bidding and is hereby incorporated into and made a part of the Contract Documents. Bidders are reminded that receipt of this addendum should be acknowledged and submitted with bidder's *Response Form*.

Specifications for the above noted Request for Bid and the work covered thereby are herein modified as follows, and except as set forth herein, otherwise remain unchanged and in full force and effect:

BID DOCUMENTS:

1. On page 15.12 of the Bid Documents under TECHNICAL SPECIFICATIONS, SECTION 02720 – AGGREGATE, replace "Type 1 (Rolled Stone) aggregate base leveling course" with "1" Clean Rock Leveling Course."
2. Clarification: The 12" leveling course (now 1" Clean Rock as stated above) called for on page 5 of the plan sheets is considered adequate stabilization unless otherwise determined by the engineer.
3. Clarification: For contractor bidding purposes, fencing shall be assumed to be replaced and temporary fencing needed, as stated in Special Provisions, page 16.1, # 1. It states "The fence on the south west side of the culvert location shall be replaced and temporary fencing should be used during the duration of the project." This line item may be deleted later pending discussions with the land owner.
4. On plan sheet, page 3 of 6, Delete last sentence of comment on upper left hand of page, "Apply 2" surface mix asphalt within 20 – foot roadway over the top of box." Replace that sentence with: "Apply sufficient full depth asphalt over top of box to maintain 2% crown and minimum 2" thickness. Flare both side edges over box 6" beyond road width on each side sloping to concrete box surface at no greater than 45 degree angle.
5. Replace BID FORM, page 5.1 in its entirety with attached BID FORM. Item # 14 was changed from Type 1 Rolled Stone Leveling Course to 1" Clean Rock Leveling Course.

By:



**Heather Turner, CPPB
Senior Buyer**

BIDDER has examined copy of Addendum #1 to Request for Bid #54-20JUN06 Boothe Lane Culvert Replacement Project, receipt of which is hereby acknowledged:

Company Name: _____

Address: _____

Phone Number: _____

Fax Number: _____

Authorized Representative Signature: _____

Date: _____

REVISED BID FORM

Boothe Lane Culvert Replacement Project
Project No. 06-449

All items shown on the project plan sheets and not included in the bid items shall be deemed incidental to the project and included in the unit prices given. In case of error in the extension, the unit price times the estimated quantity will govern.

Boothe Lane Box Culvert Base Bid					
	Description	Quantity	Unit	Unit Price	Extended Total
1.	Mobilization	1	LS		
2.	Construction Staking	1	LS		
3.	Traffic Control	1	LS		
4.	Removals	1	LS		
5.	Asphalt Paving – Bituminous Pavement (BP)-1 Surface Mix	17	TON		
6.	Asphalt Paving-Bituminous Base	24	TON		
7.	Type 1 Rolled Stone Base	270	TON		
8.	Embankment	214	CY		
9.	Type 2 Rip-Rap Rock Blanket	80	TON		
10.	Fencing	80	LF		
11.	Field Seeding/Fertilizing/Mulch	1	LS		
12.	Erosion Control Blanket	235	SY		
13.	4' x 10' Precast Box Culvert with Wing Walls and Mitered End	1	LS		
14.	1" Clean Rock Leveling Course	43	TON		
TOTAL BASE BID =					