

Engineering Surveys and Services

Consulting Engineers, Scientists, and Land Surveyors
Analytical and Materials Laboratories

1113 Fay Street
Columbia, Missouri 65201
Telephone 573-449-2646
Facsimile 573-499-1499

E-Mail ess@ESS-Inc.com
<http://www.ESS-Inc.com>

March 18, 2016

ADDENDUM #2

(Sheet 1 of 5)

to

FIRST CHRISTIAN CHURCH PARKING LOT ADDITION In Columbia, Missouri

Contract Documents for the above noted project and the work covered thereby are herein modified as follows, and except as set forth herein, otherwise remain unchanged and in full force and effect.

This Addendum forms a part of the Contract documents. It supplements and modifies them as follows:

1) RESPONSE TO QUESTIONS FOLLOWING PRE-BID MEETING:

- a. The light pole bases have been detailed in Addendum #1.
- b. The Contractor shall be responsible for providing the Site Lighting Certification for the project. The certification shall be conducted per the requirements of the City of Columbia.
- c. The Contractor shall be responsible for providing all construction staking and material testing for the project, in accordance with the Project Specifications.
- d. The concrete pad for the bike rack shall follow the construction sidewalk detail, provided on Sheet 3.01 of the Civil Plans. The bicycle rack shall be a galvanized Huntco BR5 bicycle rack (See attached specification), or approved equal.
- e. The trees specified within the alternate (5), are located at the northeast corner of the Church property. The locations have been specified within the attached document (See Tree Locations Exhibit). Please note that the amount of trees to be removed may change, therefore the "per each" unit cost provided within the bid response shall represent any Locust tree at the site.

2) BID RESPONSE (SECTION 4):

- a. A revised Bid Form has been included to incorporate items noted above. The new Bid Form, dated March 19, 2016, shall be included in Section 4 of Project Documents. The previous Bid Form, dated March 10, 2016, shall be removed from the Project Documents.

Engineering Surveys and Services

Consulting Engineers, Geologists, and Land Surveyors
Analytical and Material Laboratories
1113 Fay Street
Columbia, Missouri 65201

Telephone 573-449-2646
Facsimile 573-449-1499

E-Mail ess@ESS-Inc.com
<http://www.ESS-Inc.com>

SITE WORK BID FORM

Date: December 21, 2015 **Revised Date:** 19-Mar-16
Project: First Christian Church (FCC) Parking Lot Improvements
Description: Parking addition (14 stalls) within the southwest corner of the FCC property
Project No.: 13040
Notes: 1. The Contractor is responsible for obtaining meter bags from City of Columbia Public Works Department, including any associated fees.

Item	Description	Quantity	Unit	Unit Price	Total
1.00	SITEWORK				
1.01	Strip Topsoil (6") and Stockpile	50	C.Y.		
1.02	Respread Topsoil	50	C.Y.		
1.03	Soil Undercut, Off-site Disposal, Haul Off	400	C.Y.		
1.04	Concrete Washout Pit (incl. maintenance)	1	Each		
1.05	Silt Fence - Reinforced (incl. maintenance)	81	L.F.		
1.06	Sediment Log/Gutterbuddy Inlet Protection (including maintenance)	1	Each		
1.07	Permanent Seeding/Mulching	1	Lump Sum		
1.08	Standard Duty Asphalt (incl. base)	485	S.Y.		
1.09	Asphalt Mill & Overlay for ADA Improvements	69	S.Y.		
1.10	Reinforced Concrete Sidewalk ADA Ramp (with truncated domes)	1	Each		
1.11	24" Wide Concrete Curb and Gutter	239	L.F.		
1.12	Striping (2 coats)	553	L.F.		
1.13	Painted Accesible Symbol	2	Each		
1.14	Remove & Reinstall ADA Sign	2	Each		
1.15	Install New Light Pole, Base, and Fixture	2	Each		
1.16	Parking Lot Light Conduit and Wiring (less than 600' from panel)	130	L.F.		
1.17	Weatherproof Junction Box for Lighting	1	Lump Sum		
1.18	2" Caliper Tree	5	Each		

SITE WORK BID FORM

Date: December 21, 2015 **Revised Date:** 19-Mar-16
Project: First Christian Church (FCC) Parking Lot Improvements
Description: Parking addition (14 stalls) within the southwest corner of the FCC property
Project No.: 13040
Notes: 1. The Contractor is responsible for obtaining meter bags from City of Columbia Public Works Department, including any associated fees.

Item	Description	Quantity	Unit	Unit Price	Total
1.19	Landscaping Shrubs, Flowers, Etc.	1	Lump Sum		
1.20	Mobilization and Bonds	1	Lump Sum		
1.21	Traffic Control (Sidewalk Signs/Barriers)	1	Lump Sum		
1.22	Bicycle Rack & Pad	1	Lump Sum		
SUBTOTAL:					
2.00	DEMOLITION & PERMIT FEE				
2.01	Site Prep., Clearing, Grubbing, Stump & Tree Removal (8)	1	Lump Sum		
2.02	Asphalt and Curb Removal	91	S.Y.		
2.03	Concrete Wall Demolition (2' Average Height)	260	L.F.		
2.04	Concrete Sidewalk Demolition	188	S.Y.		
2.05	Concrete Stair Demolition	16	S.Y.		
2.06	Brick Paver Demolition	4	S.Y.		
SUBTOTAL:					
3.00	CONSTRUCTION STAKING, CERTIFICATIONS, & MATERIAL TESTING				
3.01	Construction Staking	1	Lump Sum		
3.02	Construction Material Testing per Project Specifications	1	Lump Sum		
3.03	Site Certifications per City of Columbia(ADA & Site Lighting)	1	Lump Sum		
Total of All Base Bid Prices:					
4.00	ADD ALTERNATE				
4.01	Remove Cypress Trees on Church Property & Replace w/ a Different Tree Species	5	Each		
SUBTOTAL:					
Total of Base Bid & Alternate:					


The BR Series Bike Rack

BR3, BR5, BR7, BR9, BR11 and BR13
Model numbers indicate maximum bike capacity.


Each unit is constructed of 2.375"(6.0 cm)O.D. 2"(5.0 cm)I.D. x 0.154"(.39 cm) wall
ASTM *schedule 40* steel pipe.

All BR Series racks are 36"(91.4 cm) or an optional 42"(106.7 cm) high.


- Mounting Options (see detail)
 - Flange Mount
 - Free-Standing
 - In-Ground
- Choice of three finishes:
 - Hot Dipped Galvanized
 - Powder Coating (weather resistant Polyester TGIC, 6-8 mils thick) in an unlimited range of colors.
 - Thermoplastic Coating (10-12 mils thick) in red, black, green, blue, gray, white, yellow and brown.




BR3 35 lbs.




BR5 60 lbs.




BR7 80 lbs.



BR9 120 lbs.



BR11 135 lbs.



BR13 155 lbs.

MOUNTING OPTIONS

FLANGE MOUNT

4"x1/2" anchor bolts
SIDE VIEW

TOP VIEW

IN-GROUND MOUNT

12"
6"

FLANGE COVERS
"The Finishing Touch"



***TREE LOCATION EXHIBIT
FIRST CHRISTIAN PARKING LOT IMPROVEMENTS
COLUMBIA, BOONE COUNTY, MISSOURI
MARCH 19, 2016***

Engineering Surveys and Services

1113 Fay Street, Columbia, Missouri 65201
573 - 449 - 2646 | www.ess-inc.com

Missouri Engineering Corporation # 2004005018



ES&S NO. 13040