37-01OCT20 - Mold Remediation Project in the Boone County Assessor's Office BID TABULATION PRICING Provide pricing for the timeline that you outline in 4.2.		Stan Morris Construction	CATCO / An Interstate Restoration Company	ServePro of Columbia	Midwst Assbestos Abatement Corp.
4.1.	Mold Remediaion Service - lump sum "shall not exceed" project price	\$12,500.00	\$16,248.00	\$17,798.40	\$46,800.00
4.2.	How much time is needed by the Contractor to complete the entire project from start of project until completion? Describe in detail how you would perform the entire project (nights, weekends, holidays, etc). Include cleaning, reconstruction, air quality check, etc.). Include your recommended, detailed timeline with dates (include, if possible, working on project over three-day weekened of October 9-13). If you prefer, you may attache the narrative on how this would be accomplished.	3-5 days	Arrive 10/9/20 to set-up containment. Begin 10/10/20, complete the cleaning and sealing process. Begin drywalling. 10/11/20 complete drywall and taping. Clean containment and outside of the containment. 10/12/20 complete the cleaning and painting.	Start 10/9/20 Set up containment, establish negative air space, remove contaminated building materials, cleaning surfaces, drying the effecte areas if wet aterials are discofered, conducting post-remediation evaluation, reconstruction. 10/11/20 final cleaning and through 10/12/20 alloted for County to complete 9 & 11. 10/12-10/13 air smapling, air machines run 24-48 hours. 10/16-10/18 reconstruction if pass air test.	4-7 days. Egin 10/9/20 to mobilize, build containment, drywall removal, foam insulation removal, carpet square removal. 10/10/20 containment to be HEPA vacuumed, cleanred, sanitized, and encapsulated with an anti-microbial encapsulant. Scrub using HEPA negative air machines. 10/11/20 conduct visual inspection and collect final air samples. 10/12 - 10/14/20 reconstruction (if air samples passes)
4.3.	Subcontracting" If Vendor propose to use subcontractors for this work, list the names of the firms and the work to be assigned.	n/a	Drywall: John Bender Drywall	Clearance Testing: Nick's Inspection Services	Visual Inspection/Air Clearance/Reporting: Farmer Environmental